



SECTION 05 73 00

ORNAMENTAL HANDRAILS AND RAILINGS

Show hidden Specifier Notes for best results

PART 1 GENERAL

1.01 SUMMARY

- A. Section Includes: X-TEND® CXS Stainless Steel Flexible Mesh Handrail Infill
- B. Related Sections:
 - 1. Section 4 - Masonry Anchoring and Reinforcing
 - 2. Section 5 - Metal Stairs
 - 3. Section 5 - Metal Railings
 - 4. Section 5 – Decorative Metal Railings
 - 5. Section 13 – Athletic and Recreation Safety Netting
 - 6. Section 32 – Exterior Fences and Gates

1.02 SYSTEM DESCRIPTION

- A. Performance Requirements: Provide Stainless Steel flexible Mesh Guardrail Infill and mounting hardware which have been manufactured and installed to meet or exceed manufacturer's and project performance criteria.

1.03 SUBMITTALS

- A. Submit listed submittals in accordance with Conditions of the Contract and Division 1 Submittal Procedures Section.
- B. Product Data: Submit Manufacturer's product data sheet for specified products.

- C. Shop Drawings: Show layout, sizes, dimensions, details, and installation of railing frame components. Include mesh aperture and rope dimensions, cable and mesh attachment hardware, tensioning devices, mounting methodology.
- D. Samples: Submit samples of mesh and support hardware, as required.
- E. Quality Assurance/Control Submittals:
 - 1. Test reports: Submit any test report demonstrating compliance with intended use and code requirements.
 - 2. Certificates: Submit manufacturer's certificate that product meets or exceeds specified requirements
- F. Closeout Submittals: Submit the Following:
 - 1. Warranty: Submit manufacturer's standard warranty documents
 - 2. Maintenance Data: Include manufacturer's standard cleaning and maintenance instructions to avoid detrimental actions to finishes and performance.

1.04 QUALITY ASSURANCE

- A. Qualifications:
 - 1. Installer Qualifications: Installer should be experienced in performing work of this section and should have specialized in installation of work similar to that required for this project.
- B. Regulatory Requirements and Approvals:
 - 1. [Code Agency Name]
 - a) [Report or Approval Description]
- C. Mock-Ups: Install at project site or appropriate location a job mock-up using acceptable products and manufacturer approved installation methods. Obtain Owner's and Architect's approval of product, application, and workmanship standards. Comply with Division 1 Quality Control (Mock-Up Requirements) Section.
 - 1. Mock-Up Size: [Specify mock-up size and fixation requirements].
 - 2. Maintenance and Disposal: Maintain mock-up during construction for workmanship comparison.
 - a) Removal: Remove and legally dispose of mock-up when no longer required.
 - b) Incorporation: Mock-up may be incorporated into final construction upon Owner's approval.
- D. Pre-Installation Meetings: Conduct meetings with [Contractor, Architect, Fabricator, Installer and any other subcontractors] whose work involves railing system to verify project requirements, framing and support conditions, mounting surfaces, manufacturer's installation instructions, and warranty requirements. Comply with Division 1 requirements.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. General: Comply with Division 1 Product Requirements Sections Ordering: Comply with manufacturer's ordering instructions and lead time requirements to avoid construction delays.
- B. Delivery: Deliver in manufacturer's original, unopened, undamaged containers, identification labels intact.
- C. Storage and Protection: Store materials protected from exposure to harmful weather conditions and at temperature and humidity conditions recommended by manufacturer. Store cartons and panels in a secure location in a dry place at the project site.

1.06 WARRANTY

- A. Manufacturer's Warranty: Submit, for Owner's acceptance, manufacturer's standard warranty document executed by authorized company official.

PART 2 PRODUCTS

2.01 X-TEND® CXS Series STAINLESS STEEL FLEXIBLE MESH HANDRAIL INFILL

- A. Manufactured and sold by: Carl Stahl DécorCable Innovations, Inc., 2401 International Pkwy., Ste. B, Woodridge, IL USA 60517. Tel: 312-474-1100, Fax: 312-474-1789, E: sales@decorcable.com, Web: www.decorcable.com.
- B. Proprietary Products/Systems: X-TEND® Stainless Steel Flexible Mesh Handrail Infill
 - 1. Material: Type 316 stainless steel 7x7 wire rope joined with 316 stainless steel ferrules.
 - 2. Cable Diameter x Mesh Aperture Dimensions
 - a) 1.5mm x 35mm, Stock #CX030035-S
 - b) 1.5mm x 40mm, Stock #CX030040-S
 - c) 1.5mm x 50mm, Stock #CX030050-S
 - d) 1.5mm x 60mm, Stock #CX030060-S
 - e) 1.5mm x 70mm, Stock #CX030070-S
 - f) 1.5mm x 80mm, Stock #CX030080-S
 - g) 1.5mm x 100mm, Stock #CX030100-S
 - 3. Direction (Grain) of X-tend Mesh:
 - a) Horizontal Mesh Direction for Rectangular Frame Shapes.
 - b) Horizontal Mesh Direction for Diagonal Frame Shapes.
 - 4. Support Frame Style
 - a) Round or Square Tubular Edge Supports constructed of Wood, Aluminum, Mild, or Stainless Steel. Supports to be spaced no more than 5 feet apart, depending on composition and size of support tubing.
 - b) I-SYS INOX 7x7 (or 7x19) construction Stainless Steel Wire Rope. Supports to be spaced no more than 5 feet apart, depending on size and construction of support ropes.

2.02 PRODUCT SUBSTITUTIONS

- A. Substitutions: No substitutions permitted.

2.03 FITTINGS AND ACCESSORIES

- A. General: Attachment Cable Material: Type 316 stainless steel 7x7 (or 7x19) wire rope.
- B. Accessories: Provide grommet, bushings, washers, swaging ferrules, studs, receivers, fittings and other components as required for system installation.

2.04 FABRICATION

- A. Infill Construction: Infill panels shall be dimensioned and manufactured to specified size and labeled according to installer's specifications.

PART 3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS

- A. Compliance: Comply with manufacturer's product data, including product technical bulletins, product catalog installation instructions and product carton instructions for installation.

3.02 EXAMINATION

- A. Site Verification of Conditions: Verify condition of railing and post system which has been previously installed under other sections, to ensure it is acceptable for product installation in accordance with manufacturer's instructions. Do not begin installation until backup surfaces are in satisfactory condition.

3.03 PREPARATION

- A. Supply items required to be cast into concrete or embedded in masonry with setting templates, to appropriate Sections.
- B. Take field measurements after permanent end terminations are in place and prior to preparation of shop drawings and fabrication, to ensure fitting of work.

3.04 INSTALLATION

- A. Install mesh infill system in accordance with manufacturer's instructions and the approved shop drawings.
- B. Provide anchorage devices and fittings to secure to in-place construction; including threaded fittings for concrete inserts, toggle bolts and through-bolts. Install mesh panel infill system plumb, level, square, and taut.
- C. Anchor railing system to mounting surfaces as indicated on the drawings.
- D. Separate dissimilar materials with bushings, grommets or washers to prevent electrolytic corrosion.
- E. Use manufacturer's supplied mounting hardware.
- F. Terminate and tension mesh panels in accordance with manufacturer's instructions.
- G. Ensure mesh is clean, and without waves, kinks, or sags.
- H. Adjust frame support cable tension and connecting hardware.

3.05 CLEANING

- A. Remove temporary coverings and protection of adjacent work areas.
- B. Clean installed products in accordance with manufacturer's instructions before owner's acceptance. Do not use chlorine-based or abrasive cleaners.
- C. Remove from project site and legally dispose of construction debris associated with this work.

3.06 PROTECTION

- A. Protection: Protect installed product from damage during subsequent construction activities.

END OF SECTION