

## **SECTION 32 94 00**

# X-TEND® STAINLESS STEEL FLEXIBLE MESH PLANT SUPPORT SYSTEM

Show hidden Specifier Notes for best results

# PART 1 GENERAL

#### 1.01 SUMMARY

- A. Section Includes:
  - 1. Stainless Steel Wire Rope Assemblies
  - 2. Stainless Steel Fittings, Anchors, Hardware, and Accessories
- B. Related Sections:
  - 1. Section 4 Masonry Anchoring and Reinforcing
  - 2. Section 5 Stainless Steel Wire Rope Assemblies
  - 3. Section 32 Site Improvements
  - 4. Section 32 Planting Accessories

#### 1.02 SYSTEM DESCRIPTION

- A. Performance Requirements: Provide Stainless Steel Cable Railing System and mounting hardware which have been manufactured and installed to meet or exceed manufacturer's and project performance criteria.
- 1.03 SUBMITTALS
  - A. Submit listed submittals in accordance with Conditions of the Contract and Division 1 Submittal Procedures Section.
  - B. Product Data: Submit Manufacturer's product data sheet for specified products.

- C. Shop Drawings: Show layout, sizes, dimensions, details, and installation of railing frame components. Include Details of rope attachment, tensioning methods, hardware, and tensioning and mounting methodology.
- D. Samples: Submit samples of rope and/or hardware, as required by specifier.
- E. Quality Assurance/Control Submittals:
  - 1. Test reports: Submit any test report demonstrating compliance with intended use and code requirements.
  - 2. Certificates: Submit manufacturer's certificate that product meets or exceeds specified requirements
- F. Closeout Submittals: Submit the Following:
  - 1. Warranty: Submit manufacturer's standard warranty documents
  - 2. Maintenance Data: Include manufacturer's standard cleaning and maintenance instructions to avoid detrimental actions to finishes and performance.

### 1.04 QUALITY ASSURANCE

- A. Qualifications:
  - 1. Installer Qualifications: Installer should be experienced in performing work of this section and should have specialized in installation of work similar to that required for this project.
- B. Regulatory Requirements and Approvals:
  - 1. [Code Agency Name]
    - a) [Report or Approval Description]
- C. Mock-Ups: Install at project site or appropriate location a job mock-up using acceptable products and manufacturer approved installation methods. Obtain Owner's and Architect's approval of product, application, and workmanship standards. Comply with Division 1 Quality Control (Mock-Up Requirements) Section.
  - 1. Mock-Up Size: [Specify mock-up size and fixation requirements].
  - 2. Maintenance and Disposal: Maintain mock-up during construction for workmanship comparison.
    - a) Removal: Remove and legally dispose of mock-up when no longer required.
    - b) Incorporation: Mock-up may be incorporated into final construction upon Owner's approval.
- D. Pre-Installation Meetings: Conduct with [Contractor, Architect, Fabricator, Installer and any other subcontractors] whose work involves cable railing system to verify project requirements, framing and support conditions, mounting surfaces, manufacturer's installation instructions, and warranty requirements. Comply with Division 1 requirements.

#### 1.05 DELIVERY, STORAGE, AND HANDLING

- A. General: Comply with Division 1 Product Requirements Sections Ordering: Comply with manufacturer's ordering instructions and lead time requirements to avoid construction delays.
- B. Delivery: Deliver in manufacturer's original, unopened, undamaged containers, identification labels intact.
- C. Storage and Protection: Store materials protected from exposure to harmful weather conditions and at temperature and humidity conditions recommended by manufacturer. Store cartons and panels in a secure location in a dry place at the project site.

#### 1.06 WARRANTY

A. Manufacturer's Warranty: Submit, for Owner's acceptance, manufacturer's standard warranty document executed by authorized company official.

# PART 2 PRODUCTS

- 2.01 X-TEND® STAINLESS STEEL MESH PLANT SUPPORT SYSTEM
  - Manufactured and sold by: Carl Stahl DécorCable Innovations, Inc., 2401 International Pkwy., Ste.
    B, Woodridge, IL USA 60517. Tel: 312-474-1100, Fax: 312-474-1789, E: <u>sales@decorcable.com</u>, Web: <u>www.decorcable.com</u>.
  - B. Proprietary Products/Systems: X-TEND® Brand Stainless Steel Mesh Plant Support System.
    - 1. Material:
      - a) Cable: Type 316 stainless steel 7x7 wire rope.

b) Mesh: AISI 316 stainless steel 7x7 wire rope joined with AISI 316 stainless steel or tinned copper ferrules

- c) Fittings, Anchors, Hardware, and Accessories: AISI 304, 316 or 316L stainless steel.
- 2. Stainless Steel Wire Rope 7x7 construction:
  - a) 4mm (5/32"), 2000 lbs. MBL, 6.85mm<sup>2</sup> MQ Stock #820-0400
  - b) 5mm (3/16"), 3135 lbs. MBL, 10.70mm<sup>2</sup> MQ Stock #820-0500
  - c) 6mm (1/4"), 4500 lbs. MBL, 15.42mm<sup>2</sup> MQ Stock #820-0400
- 3. Rope End Fittings, Terminals, and Tensioners:
  - a) External Thread-Swaged RH Stock #850, LH Stock #855
  - b) External Thread F30 Hammer Swaged-RH Stock #950, LH Stock#951
  - d) External Thread-Field Installed RH Stock #850, LH Stock #850
  - e) Turnbuckle-Specify Type-Stock #875
  - f) Turnbuckle with Swaged External Thread ends Stock #829
  - g) Turnbuckle with F30 Hammer Swaged External Thread ends Stock #829
- 4. Support Components:
  - c) Spacer Bar w/M8 Internal Thread-Specify Length-Stock #919.
  - d) Cross Clamp-Specify Length-Stock #919.
  - e) Spacer Bar-Unthreaded 8mm Internal Bore-Specify Length-Stock #919.
  - f) Spacer Bar Support Link-Stock #834
  - g) Clamp Screw for M8 Spacer Bars-Specify Size-Stock #923

- h) Ground Plate- Unthreaded-Stock #836
- i) Cover Disk with Internal M8 Threads -Stock #836
- j) Eye Bolt-Stock #837
- k) Eye Nut-Stock #838
- I) Fork Bracket-Stock #834
- m) SS Adjustable Support to for EIFS facades-Stock #897
- h) Plastic Pipe Support for EIFS facades-Stock #897-0690
- i) Sealing Disk for Pipe Support-Stock #897-9
- j) Sealing Ring for Pipe Support-Stock #897-8
- 5. X-TEND® Stainless Steel Mesh Plant Support Panels:
  - a) 1.5mm x 80mm, Stock #CX015080
  - b) 1.5mm x 100mm, Stock #CX015100
  - c) 1.5mm x 120mm, Stock #CX015120
  - d) 1.5mm x 140mm, Stock #CX015140
  - a) 1.5mm x 160mm, Stock #CX015160
- 6. Attachment Anchors and Hardware:
  - a) Dual Thread Screw-RH Stock #878, LH Stock #877
  - b) Rampa Nut for Wood, Stock #803
  - c) Threaded Rod (Headless Screw)-RH Stock #882, LH Stock #883
  - d) Wall Anchor for Masonry with Internal Thread RH Stock #803
  - e) Wall Anchor for Masonry with External Thread RH Stock #803

#### 2.02 PRODUCT SUBSTITUTIONS

A. Substitutions: No substitutions permitted.

#### 2.03 FITTINGS AND ACCESSORIES

A. Accessories: Provide grommet, bushings, nuts, washers, turnbuckles, fittings and other components as required for system installation

### 2.04 FABRICATION

- A. Stainless Steel Cables and Fittings shall be dimensioned and fabricated to specified size and labeled according to shop drawings and installer's specifications.
- B. Preassemble items in shop to greatest extent practicable to minimize assembly at project site. Disassemble units only to extent necessary for shipping and handling limitations. Mark units for reassembly.

## **PART 3 EXECUTION**

#### 3.01 MANUFACTURER'S INSTRUCTIONS

A. Compliance: Comply with manufacturer's product data, including product technical bulletins, product catalog installation instructions and product carton instructions for installation.

## 3.02 EXAMINATION

A. Site Verification of Conditions: Verify condition of any support system which has been previously installed under other sections, to ensure it is acceptable for product installation in accordance with manufacturer's instructions. Do not begin installation until backup surfaces are in satisfactory condition.

#### 3.03 PREPARATION

- A. Supply items required to be cast into concrete or embedded in masonry with setting templates, to appropriate sections.
- B. Take field measurements after permanent end terminations are in place and prior to preparation of shop drawings and fabrication, to ensure fitting of work.

### 3.04 INSTALLATION

- A. Install cable railing system in accordance with manufacturer's instructions and the approved shop drawings.
- B. Provide anchorage devices and fittings to secure to in-place construction; including threaded fittings for concrete inserts, toggle bolts and through-bolts. Install mesh panel system plumb, level, square, and taut.
- C. Anchor system to mounting surfaces as indicated on the drawings.
- D. Separate dissimilar materials with bushings, grommets or washers to prevent electrolytic corrosion.
- E. Use manufacturer's supplied mounting hardware.
- F. Terminate and tension cable system in accordance with manufacturer's instructions.
- G. Ensure ropes are clean, and without kinks or sags.
- H. After final adjustment provide tamper resistant locktight materials on all fittings.

#### 3.05 CLEANING

- A. Remove temporary coverings and protection of adjacent work areas.
- B. Clean installed products in accordance with manufacturer's instructions before owner's acceptance. Do not use chlorine-based or abrasive cleaners.
- C. Remove from project site and legally dispose of construction debris associated with this work.

# 3.06 PROTECTION

A. Protection: Protect installed product from damage during subsequent construction activities.

#### END OF SECTION